9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale excluding the 10 per cent deposit paid for the lot at the time of the sale ; and no timber shall be removed from the depot unless a permit is obtained from the Forest Officer in charge of the depot. The earnest money will not be adjusted towards the value of timber until 90 per cent of the purchase money over and above the security deposit has been paid. Interest at 9% per annum will be levied on all arrears of amounts permitted to be paid after the due dates.

10. Timber purchased should be removed as early as possible, and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase will remain in the depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser, so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification, dated 16th December 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 20th January 1936 for constructing main drain at Chamarajanagar Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1936.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing main drain at Chamarajanagar Town" in default of which the tenders will be rejected.

5 The final acceptance of any tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for constructing Main Drain in Chamarajanagar.

No.	Particulars	Unit	Quantity
1	Constructing main drain of trapezoidal section $\frac{3\frac{1}{2}'+2\frac{1}{2}'}{2}\times 2\frac{1}{2}'$ with side walls.		
	(*a*) $\frac{1\frac{1}{2}'+2'}{2}\times 2\frac{1}{2}'$ of size stone in surki mortor on 1 foot thick surki concrete bed with $1\frac{1}{4}'$ diameter semicircular channel in the centre, the curved surface being plastered with $\frac{1}{2}''$ cement plastering and flat surface covered with 3″ thick burnt stone slabs and the joints cement-pointed including earthwork as per design	R.ft.	850
2	Constructing main drain of trapezoidal section $\frac{4'+3'}{2}\times 3'$ with side walls		
	$\frac{1\frac{1}{2}'+2'}{2}\times 3'$ of size stone in surki mortor on 1 foot thick surki concrete bed with $1\frac{1}{2}'$ diameter semicircular channel in the centre, the curved surface being plastered with $\frac{1}{2}''$ cement plastering and flat surface covered with 3″ thick burnt stone slabs and the joints cement-pointed, including earthwork, as per design	,,	500

B. R. GARUDACHAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated the 18th December 1935.

Notice is hereby given that the abstract estimates for the "Construction of Telephone Exchange Buildings at Bangalore" as published in pages 2239 to 2243 of Part VI of the *Mysore Gazette* of the 12th December 1935, is modified as hereunder and therefore the tender for the work should be submitted in printed forms as per present modifications only.

2. This form as modified supersedes the original abstract portion and the last date of receiving tenders is consequently postponed to 11th January 1936. The other conditions such as earnest money deposit, etc., remain unchanged.

Abstract estimate of quantities for constructing Telephone Exchange Buildings at Bangalore (modified).

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
	GROUND FLOOR.		Rs. a. p.		
1	Excavating foundations and filling in basement with watering and consolidating	C.yd.	0 4 6	485	
2	Broken stone jelly concrete in lime mortar with tamping in layers of 6″ thick	C.ft.	0 4 0	4,915	
3	Size stone in mortar with bond stones, 6 ft. apart for foundations	,,	0 4 6	4,885	
4	Size stone in mortar with bond stones, 6′ apart all quoins neatly dressed 2″ wide for basement	,,	0 5 0	878	
5	Burnt stone slabs 6″ thick, two line dressed for the outer walls of basement and one line dressed for all other faces	S.ft.	0 6 0	606	
6	Burnt stone slabs, 6″ thick, one line dressed for cills and lintels of windows, doors, and ventilators and for inner walls of basement	,,	0 5 0	963	
6 (a)	Cut stone skirting 9″ high 7″ thick and in length to suit two line dressed	R.ft.	0 12 0	250	

6 C